

ADDENDUM #1



SIOUX FALLS

4609 S. Techlink Circle ■ Sioux Falls, SD 57106
Ph: (605) 362-3753 ■ Fax (605) 362-3759

Date: December 18, 2019
To: All planholders
From: West Plains Engineering **WPE#:** BS19089
Project: Blue Dog Hatchery Moisture Mitigation **Location:** Day County, SD

TO: All prime contract bidders and all others to whom Drawings and Specifications have been issued by the Engineer. Acknowledge receipt of the Addendum by inserting its number and date on the Bid Form. Failure to do so may subject bidder to disqualification. This Addendum forms a part of the Contract Documents. It modifies them as follows:

PRODUCT APPROVALS:

The manufacturers and products, which are listed in the following texts, are approved for bidding. Final acceptance is contingent upon receipt and approval of final shop drawings. Manufacturer shall conform to all warranties, performances, size, etc., as the item specified. The burden of proof of the merit of the proposed substitution is upon the proposer. Those items not specifically listed by addendum shall not be approved for bidding.

<u>SECTION</u>	<u>DESCRIPTION</u>	<u>MANUFACTURER</u>
23 7223	Packaged Air to Air Energy Recovery Units	Addison, Valent Air Management Systems

SPECIFICATIONS:

GENERAL CONDITIONS

- 1. In Exhibit "B Sample of Sealed Envelope" replace "2:00 PM" to "3:15 PM"

SECTION 23 0010

- 1. Delete paragraph 23 0010 1.26

SECTION 23 3100

- 1. Delete paragraph 23 3100 3.03.

DRAWINGS:

SHEET M6

- 1. In the ROOFTOP UNIT SCHEDULE replace the supply winter LAT WB from 39 degrees to 26 degrees.
- 2. In the FURNACE SCHEDULE remove specific note 5 from furnace F-2 and F-3.
- 3. In the FURNACE SCHEDULE replace specific note 7 with the following; "7. PROVIDE A COMPLETE MANUFACTURERS RECOMMENDED VENT SYSTEM. TERMINATE NEW VENTING THROUGH EXISTING ROOF PENETRATION."
- 4. In the CONDENSING UNIT SCHEDULE replace the SEER rating of "14" with "13".

STRUCTURAL:

- 1. See attached addendum from Structural Engineering Associates.

End of Document



STRUCTURAL ENGINEERING
ASSOCIATES

Addendum 1 Structural Items

Date: December 18, 2019

From: Greg Hannestad, P.E.

To: Isaac Anderson, P.E. West Plains Engineering

Re: Moisture Mitigation and HVAC Upgrades
Blue Dog State Fish Hatchery
Day County, SD

Job No.: SDGF&P Project: BluD20Wa
WPE Project: BS19089

Following are the structural items for this addendum:

ITEM 1: **Drawing S1 – Roof Framing Plan:**

- A. At 1/S1 Roof Framing Plan: delete note “PRECAST CONCRETE BEAM REQUIRES ADDITIONAL CAPACITY FOR NEW LOADS. REFER TO 2/S1.”
- B. At 2/S1 ADDITIONAL CAPACITY REQUIRED AT PRECAST BEAMS: delete 2/S1 in its entirety. The existing precast concrete beams supporting the new roof-top unit have been found to have adequate capacity to safely support the new loads.

ITEM 2: **Drawing S2 – General Structural Notes & Details:**

- A. At General Structural Note section PRECAST PRESTRESSED CONCRETE: delete note 4.

Please contact us with any questions or comments.