



SOUTH DAKOTA DEPARTMENT OF GAME, FISH AND PARKS

523 EAST CAPITOL AVENUE | PIERRE, SD 57501

ADDENDUM NO. 1 09/12/2025

**Bank Stabilization
George S. Mickelson Trail
Pennington County, South Dakota
GFP Project No. GSMT23Pd**

Bid Opening Date: September 18, 2025, 3:30 PM CT
Department of Game, Fish and Parks
2nd Floor, Foss Building
523 East Capitol
Pierre, South Dakota 57501-3182

Owner: State of South Dakota
Department of Game, Fish and Parks

Scope of this Addendum:

The following becomes a part of the original plans and specifications, taking precedence over the items that may conflict. The bidder shall note receipt and make acknowledgment of the addendum on his bid form, incorporating its provisions in his bid.

1. Additional Plan Notes/Clarification:

Haul Routes

The Contractor will be responsible for determining any haul routes from the material source(s) to the project site including any agreements necessary with respective governmental agencies for maintenance and restoration of the routes.

It shall be the responsibility of the Contractor to prepare the haul route, maintain the haul route in a good condition satisfactory to the governing agency and upon completion of its use, restore the haul route to a condition at least equal to that which existed at the time hauling operation began. The fact that other general and normal traffic have used the haul route or a portion of it concurrently shall not relieve the Contractor of his obligation to maintain and restore the haul route as recommended.

Notification to Project Engineer

The Contractor is required to notify the Project Engineer at least 10 days prior to beginning construction activities.



SOUTH DAKOTA DEPARTMENT OF GAME, FISH AND PARKS

523 EAST CAPITOL AVENUE | PIERRE, SD 57501

The Project Engineer shall be notified before any over runs from plans quantities are approved.
Project site limits will be marked by the Owner.

Riprap Source and Specification

Stone for riprap shall meet the gradation requirements of Section 830.1 of the SDDOT Standard Specifications for Roads and Bridges, 2015 Edition. Riprap shall be durable, clean stone, free of dirt, vegetation, or other foreign matter. Field stone for use as riprap shall have a minimum of 2 crushed faces, mechanically or naturally, as defined under SD 211 "Method of Test Percentage of Crushed Particles".

Riprap gradation will be sent to the Project Engineer after bid letting for approval.

Stockpile/Staging Location

The Rochford Trail Head parking lot is an option for stockpiling and staging materials/equipment for the project.

Tyler Ulrich

Tyler Ulrich (Sep 12, 2025 09:30:11 CDT)

Tyler Ulrich
Engineer III

09/12/2025

Date