

## ADDENDUM | No. 1

<b>PROJECT</b>	Lake Andes Outlet Pipe, Lake Andes, SD, GPF Project No. OSE#G2123-38X/ARPA
<b>BID DATE</b>	3:30 PM                      CT                      6/4/2024
<b>BID LOCATION</b>	South Dakota Department of Game, Fish and Parks Engineering Section Foss Building, 523 East Capitol Ave., Pierre, SD 57501-3182 Video Link: <a href="https://gfp.sd.gov/bids-contracts/">https://gfp.sd.gov/bids-contracts/</a>
<b>ISSUE DATE</b>	5/28/2024
<b>NOTICE</b>	Failure to acknowledge all addenda in the BID may cause rejection of the BID. See Instructions to Bidders.

### SCOPE OF THIS ADDENDUM

The following becomes a part of the original project plans and drawings, taking precedence over the items that may conflict. The bidder shall note receipt and make acknowledgment of the Addendum on his/her bid form, incorporating its provision in his/her bid.

### ITEM NO. 1

*Question:* I see storm structures that appear to be cast in place, but the bid schedule suggests it would be precast. Looking for clarification.

*Answer:* The costs for the manhole base for each of the three (3) manholes to be installed is incidental to the contract unit price per each for 60" Manhole. The manhole base and lid are detailed as cast-in-place concrete while the riser is precast concrete pipe sections.

Precast base sections and lids will be allowed provided that the fabricator provides their design and check design of the bases and lids.

The following is added to the General Notes in the Storm Drainage section in the plans:



**60" MANHOLE**

MANHOLE NO.	BASE SECTION	*RISER SECTION	TOTAL H
3A	9.5'	19.8'	29.3'
3	9.5'	19.1'	28.6'
2	9.5'	7.3'	16.8'

H = HEIGHT FROM FLOWLINE TO TOP OF CAST-IN-PLACE LID  
\*FIELD VERIFY DEPTHS

INSTALL BASE SECTION FOR EACH MANHOLE AS DETAILED IN SECTION S-900 OF THESE PLANS. RISER SECTIONS FOR ACCESS WILL BE 60" REINFORCED CONCRETE PIPE WITH LID AND MANHOLE FRAME AND COVER AS DETAILED IN SECTION S-900 OF THESE PLANS. PAYMENT FOR THE BASE SECTIONS, 60" REINFORCED CONCRETE PIPE WITH LID AND MANHOLE FRAME AND COVER WILL BE INCIDENTAL TO THE CONTRACT UNIT PRICE PER EACH FOR THE 60" MANHOLE.

PRECAST BASE SECTION AND LIDS WILL BE ALLOWED PROVIDED THAT THE FABRICATOR PROVIDES THEIR DESIGN AND CHECK DESIGN OF THE BASES AND LIDS ALONG WITH THE SHOP DRAWINGS. THE DESIGN AND CHECK DESIGN WILL BE COMPLETED BY PROFESSIONAL ENGINEERS REGISTERED WITH THE STATE OF SOUTH DAKOTA AND WILL BE SUBMITTED TO BANNER ASSOCIATES, INC.

THE FABRICATOR WILL SUBMIT SHOP DRAWINGS IN ACCORDANCE WITH THE CONSTRUCTION SPECIFICATIONS TO BANNER ASSOCIATES, INC., 10 AUSTIN ST., VERMILLION, SD 57069, ([LUKEJ@BANNERASSOCIATES.COM](mailto:LUKEJ@BANNERASSOCIATES.COM)). AFTER REVIEW, CORRECTIONS (IF NECESSARY), AND APPROVAL, BANNER ASSOCIATES, INC. WILL AUTHORIZE FABRICATION, ARRANGE FOR FABRICATION INSPECTION, AND DISTRIBUTE THE SHOP DRAWING.

Lucas A Johnson, PE